

SURVEY & REMONUMENTATION

OCT 25 1993

FILED

SEP 27 8 38 AM '93

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston
(County)

Located In:

Corner Code ##

- | | | |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey | T <u>3N</u> R <u>3E</u> | <u>K-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

L.S.C. #8m^c

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Charles E Garlock, in a field survey on September 24, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 GLO witnesses to SW corner Sec. 36 T3N-R3E, Handy Twp. (K-13)
 Hick 5-N67E-29 lks.; Symore 7-N81½W-114 lks.
 / (Sycamore)
 See reverse side for corner summary of research.
 GLO notes dated: April 15, 1825, Sylvester Sibley

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found PK spike from previous witnesses and surveys by Patrick L Benton and myself.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Reset with 1½" X 36" I. Pipe with Liv. Co. Monumentation cap in Mon Box at (-0.5')
 N45E-46.14'-face of Conc. post 15" dia.
 N30E-90.98'-sp W/s U. Pole
 S45E-38.13'-sp W/s U. Pole
 N80W-192.85'-sp S/s 6" Sycamore
 East-110.62'-NW cor. Sec. 1 T2N-R3E, Iosco Twp.
 North-0.5'±-ctr. Mason Rd.

APPROVED by Livingston County Monumentation Peer Group July 21, 1993

Signed by Charles E Garlock Date 9/24/93
 Surveyor's Michigan License No. 19762

10/26/93

SERVING LIVINGSTON COUNTY
SINCE 1868

"Be Sure of Your Ground"

CHARLES E. GARLOCK

PROFESSIONAL SURVEYOR

840 EAST DAVIS ROAD
HOWELL, MICHIGAN 48843


OFFICE: (517) 546-3340

FAX: 517 546-2941


July 12, 1993

K -13: SW corner Section 36, Handy Twp. Liv. Co. MI

Did not find any old, old witness point present. Found PK spike set for corner in 1969 road survey by PL Benton, which matched witnesses to old School foundation and again used in 1986 survey for Iosco Twp. Found Iosco Twp. Sec. corner 110.62 ft. East (GLO = 89.76ft) and found PK is about 5 ft.± East of centerline of road to North. Sweep of the area found no additional irons. Location of corner was rebuilt by PL Benton from the occupation deed lines of the old School building. M W Bullock had a 1.67 ch. jog for the Iosco Twp. falling corner with the SW corner prior to 1906.



Charles E Garlock, PS



Found PK spike in Asphalt Road

SUCCESSOR TO:

MILES W. BULLOCK, L.S. (1844 TO 1926) ●

GRANT H DUNNING, P.E. (1865 TO 1928)

CLAY W. GORDON, RLS (1883 TO 1970) ●

L'LE W. MUNSELL, RLS (1904 TO 1987)