

CORNER SUMMARY

L-3: SOUTH 1/4 CORNER SECTION 1, T3N-R3E, HANDY TOWNSHIP,
LIVINGSTON COUNTY, MICHIGAN.

GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY AND NONE OF THE GLO
WITNESSES REMAIN.

M BULLOCK WITNESSES THIS CORNER IN 1875 TO THE FACE OF TWO OAKS OF
10" AND 36" DIAMETER AT 38.28 AND 54.12 FEET, MEASURES TODAY TO
CENTERLINE OF 34" AND 43" OAKS ARE 39.13 AND 52.66 FT. ALL OTHER
WITNESSES THAT REMAIN CHECK TODAY TO A FOUND 3/4" I. PIPE IN THE
CENTERLINE XING OF TWO GRAVEL ROADS. FOUND TWO ACT 74'S RECORDED
AND SEVEN ACT 132'S. MEASURES NORTH ARE 2630.28 BY BOSS AND BRADY,
2650.58 BY VERBA AND 2650.50 BY BRYAN AND MYSELF. MEASURES SOUTH
ARE 2668.96 BY HUGHES, 2668.98 BY BENTON; MEASURES EAST ARE
2639.36 BY BOSS AND ALBRIGHT, 2639.86 BY VERBA. 2639.45 BY HUGHES,
2639.62 BY BENTON AND 2638.85 BY NEWMAN. MEASURES WEST ARE
2604.36 BY CHMP AND BENTON, 2604.30 BY HUGHES, 2604.29 BY MYSELF,
2604.41 BY VERBA AND 2599.08 BY OLD SURVEY RECORDS. FOUND NO
OTHER IRONS IN THE AREA. ONE OF BULLOCKS WITNESSES SEEM TO CHECK
VERY CLOSE AND THE SECOND ABOUT 2.85 FEET OFF, BUT WOULD STILL
RECOMMEND THE USE OF THE FOUND CORNER BECAUSE OF THE SIZE OF THE
TREES AND A POSSIBLE SCRIBNERS ERROR. CORNER NOT GOOD FOR GPS.



CHARLES E GARLOCK
PS 14762
HAN96L3

T3N
R3E
L3

4