

OCT 21 1999

9

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston (County)

Located In:

Corner Code #

- 1. Public Land Survey T 3N R 3E L-3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

FILED JUL 17 2 16 PM '96 NANCY HAVILLAND REGISTER OF DEEDS LIVINGSTON COUNTY, MI 48843 L.S.C. #542M Register of Deeds Stamp & File Number

Charles E Garlock in a field survey on June 20, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration: GLO survey dated: April 15, 1825 by S Sibley DS GLO Witnesses: W07-N81W-24 lks W026-S65E-48 lks

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column J and row 3.

Additional historical data on rear of sheet

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found 1" X 12" Iron Pipe at -0.5'



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: L-3: S 1/4 cor. Sec. 1 T3N-R3E, Handy Twp. Liv.Co. MI, reset I. Pipe with 1 1/4" X 36" breakaway I. Pipe with Liv.Co. REmon Brass cap on top. S45W-39.10'-sp & tag E/s 50" Oak N60W-68.79'-sp & tag S/s 14" Hickory N60W-57.35'-face steel 4" dia. post, marker for gas line N50E-43.92'-sp & tag W/s U. Pole N45E-93.55'-SW cor. enclosed wood porch S45E-52.65'-sp & tag W/s 54" Oak Cor. on centerline Xing of Sharp & Hogback Rds.

Signed by [Signature] Date June 21, 1996

Surveyor's Michigan License No. 14762

P.A. 345 1980, APPROVED BY LIVINGSTON COUNTY PEER GROUP ON 3-27-96 CO. REP JED