


CORNER SUMMARY

B-13: S 1/4 COR. SEC. 31, T3N-R4E, HOWELL TWP. LIV. CO. MI

GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY, DS, AND NONE OF THE GLO WITNESSES REMAIN.

WITNESSED BY E GRANT (1878) AND M BULLOCK (1880)- ALL GONE. BOSS SET A PK SPIKE IN 1972, "EXISTING OCCUPATION SERVED AS EVIDENCE IN RE-ESTABLISHING CORNER". 1993 DESINE FOUND SAID PK SPIKE AND BOSS' WITNESSES CHECKED, AS THEY DID IN 1995 AND I FOUND PK SPIKE AND INLINE WITH FENCE TO THE NORTH. FOUND ONE ACT 74 AND EIGHT ACT 132'S RECORDED THAT WERE TIED TO THE CORNER. MEASURED EAST 2569.05 FT & MUNSELL HAD 2568.0 FT., MEASURED WEST 2446.83 FT. AND DESINE HAD 2447.01 FT. AND MEASURED EAST 229.61 FT. TO A FOUND MARION 1/4 CORNER THAT WAS 0.11 FT. NORTH OF THE TOWNSHIP LINE. IRON IS IN AN ASPHALT ROAD, TREES TO THE NW AND THE BALANCE BEING OPEN FOR GPS.

CHARLES E GARLOCK  
PS14762  
B13HOW95



3N-4E B13

40

FILED  
9

FEB 13 10 34 AM '96

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI  
48843

For corners in

Livingston  
(County)

Located In:

Corner Code ##

1. Public Land Survey	T	3N	R	4E	C-11
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

L.S.C.#524m

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Charles E Garlock, in a field survey on February 9, 19 996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
GLO survey dated: April 15, 1825 by S Sibley DS  
GLO witness: Tam 10-N87E-1.67 ch  
Corner in stream flowing East

Additional historical data on rear of sheet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 2" Iron pipe flush with the marsh


SURVEY &  
REMONUMENTATION

AUG 06 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11: NE cor. Sec. 31, T3N-R4E, Howell Twp. Liv. Co. MI, set 1" X 36" I. Pipe inside found 2" Iron Pipe with Liv. Co. Remon. brass cap on top at +1.0 ft.±  
N5W-64.00'-sp & tag W/s 6" Ash  
N10W-81.15'-sp & tag E/s 8" Ash  
n35W-102.98'-sp & tag E/s 6" Ash  
West-114.75'-sp & tag N/s 6" Elm  
East-40'±- West edge of stream 30' wide±  
South-6'±-remains of E-W fence line.



Signed by Charles E Garlock

Date February 10, 1996

Surveyor's Michigan License No. 14762

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

P.A. 345 1980, APPROVED BY LIVINGSTON COUNTY

PEER GROUP ON 2/7/96 CO. REP JED