

CORNER SUMMARY

F-11: NORTH 1/4 CORNER OF SECTION 33, T3N-R4E, HOWELL TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN.

GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY, AND NONE OF THE GLO WITNESSES REMAIN.

FOUND NO RECORD OF COUNTY SURVEYOR WITNESSES IN THE COURT HOUSE, BUT FOUND AN OLD MEASURE TO THE EAST OF 2640. FT. AND FOUND NO SURVEYS PRIOR TO 1990 OF THIS AREA. BOSS STATED THEY FOUND THEIR CAPPED IRON, IN 1990, AT 2651.43 FT WEST OF THE NE CORNER OF SECTION 33 WITH THE 1/8 CORNER BETWEEN NOT AT 1/2 THE DISTANCE NOR ON LINE WITH TO TWO CORNERS AND 2646.35 FT. EAST OF THE NW CORNER OF SECTION 33. SINCE THIS DATE HOWELL TOWNSHIP AS CONSTRUCTED 2 SANITARY LAGOONS IN THIS AREA, ONE OF WHICH LIES OVER AND AROUND THE N 1/4 CORNER. IN 1992 DESINE FOUND THE LAGOONS AND PLACED THE 1/4 CORNER ON PAPER, ON LINE WITH THE NW AND NE SECTION CORNERS AND AT 1/2 THE DISTANCE. I MEAS'D 5296.95 FT. BETWEEN THE SECTION CORNERS, DESINE HAD 5297.12 FT. AND BOSS ENGR HAD 5297.78 FT. BEING AS THE PROPERTY AROUND THE 1/4 CORNER IS NOW OWNED BY HOWELL TOWNSHIP, I WOULD NOW SUGGEST ESTABLISHING THE NORTH 1/4 CORNER ON LINE WITH THE SECTION CORNERS AND AT 1/2 THE DISTANCE. THEN SET TWO REFERENCE POINTS ON THE SECTION LINE, ONE LYING WEST 59.86 FT. ON TOP OF A LAGOON BERM AND WEST OF THE CENTERLINE OF A ROAD WAY AND THE OTHER 478.07 FT. EAST OF THE 1/4 CORNER ON TOP OF A BERM BETWEEN THE TWO LAGOONS. THE AREA IS OPEN AND VOID OF TREES IN ALL DIRECTIONS EXCEPT A WOODS TO THE SW ABOUT 150 FT. AWAY.



*Charles E. Garlock*



