



**SURVEY & REMONUMENTATION**

OCT 25 1993

FILED

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

OCT 12 10 18 AM '93

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI  
48843

For corners in  
Livingston  
(County)

Located In: Corner Code ##

- 1. Public Land Survey T 3N R 4E G-12  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section: S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

L.S.C.# 13m

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Charles E Garlock, in a field survey on October 8, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
GLO notes dated: April 15, 1825, S Sibley DS  
GLO witnesses: RO 10-S82 1/2E-47 lks  
WO 11-N30W-30 lks

Additional historical data on back of sheet

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 3/8" I. Rod in old fence corner hole.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set 1 1/4" X 36" I. Pipe with brass cap. (+0.5')  
East-16.92'-spike N/s 18" Hickory  
N45E-17.77'-spike W/s 36" Oak  
N30E-38.83'-spike W/s 18: Hickory  
North-14.13'-sike E/s 24" Hickory  
Remains of fence lines N, E & W.

Approved be Livingston County Monumentation Peer Group, August 18, 1993

Signed by *Charles E Garlock* Date October 9, 1993

Surveyor's Michigan License No. 14762

10/24/93