

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T 3 N R 4 E</u>	<u>K-03</u>
	T <u>    </u> R <u>    </u>	<u>          </u>
	T <u>    </u> R <u>    </u>	<u>          </u>
	T <u>    </u> R <u>    </u>	<u>          </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>          </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>          </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>          </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>          </u>

1999 MAY 21 A 9:22

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

L.S.C. #1007m

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, JACK K SMITH, in a field survey on APRIL 30, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3											●		
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1825 SIBLEY SET POST  
BLACK OAK 18 S 70° E 22.4'  
BLACK OAK 7 N 54 1/2° W 4.6'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND BOAT SPIKE IN MONUMENT BOX FROM PREVIOUS WITNESSES. THIS POSITION IS THE ONLY ONE THAT APPEARS TO HAVE BEEN USED.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-03 CORNER COMMON TO SECTIONS 1, 2, 11 AND 12, T3N, R4E, HOWELL TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN:  
SET 1 1/4" X 36" STEEL PIPE WITH 6" BREAK OFF SECTION AND LIVINGSTON COUNTY REMONUMENTATION BRASS CAP WITH SURVEYOR #35999 IN MONUMENT BOX ON CENTER LINE OF OAK GROVE ROAD.

S88°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN SOUTH SIDE 24" WALNUT  
S74°E CENTER LINE OF 1 1/4" PINE  
N22°W "X" CHISLED IN NORTH RIM OF TELEPHONE COMPANY MANHOLE  
S15°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN WEST SIDE 14" ELM

110.00'  
96.50'  
68.28'  
175.82'



Signed by [Signature]

Date 5-11-1999

Surveyor's Michigan License No. 35999