


CORNER SUMMARY

L-9: NORTH 1/4 CORNER OF SECTION 25, T3N-R4E, HOWELL TOWNSHIP,
LIVINGSTON COUNTY, MICHIGAN.

GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY, DS, AND NONE OF THE
GLO WITNESSES REMAIN.

1874 M BULLOCK WITNESSED THIS CORNER AND WITNESS TREE IS GONE.
1910 G DUNNING SET A RED STONE 6 1/2" X 6" X 7", MOWER GUARDS AND
IRON. IN 1935 C GORDON STATED NORTH 1/4 CORNER WAS 22 FEET WEST OF
A FENCE LINE INTERSECTION EAST, WEST AND SOUTH. IN 1949 L MUNSELL
FOUND THE MOWING MACHINE KNIFE IN AN EAST-WEST FENCE LINE AND 22
FEET WEST OF A FENCE CORNER WITH FENCE TO THE EAST, WEST AND
SOUTH. IN 1994 BOSS SET A 1/2" I. ROD IN THE EAST-WEST FENCE LINE
AT A POINT 22 FEET WEST OF THE FENCE LINE INTERSECTION RUNNING
EAST, WEST AND SOUTH. WE FOUND BOSS' IRON IN THE REMAINS OF THE
EAST-WEST FENCE LINE AND 22 FEET WEST OF THE FENCE CORNER.
OVERHANGING OAK TREE MAKES THE SITE UNSUITABLE FOR GPS. MEASURES
EAST ARE 2614.92 AND 2619.54 BY OLD SURVEY RECORDS AND I MEASURED
2642.22. MEASURES WEST ARE 2614.92 BY OLD SURVEY RECORDS, 2648.0
BY C GORDON AND I MEASURED 2646.35. FOUND NO ACT 74'S RECORDED
AND ONLY ONE ACT 132 RECORDED. RECOMMEND CONTINUED USE OF THE
FOUND CORNER.



CHARLES E GARLOCK
PS 14762
HOW96L9

T3N-R4E
L9

7

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston
(County)

Located In:

Corner Code ##

- | | | |
|---------------------------------------|-------------------------|-------------|
| 1. Public Land Survey | T <u>3N</u> R <u>4E</u> | <u>L-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

SEP 1 3 29 PM '94
 NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI
 48843

FILED

L.S.C.# 250m
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		19		20		21		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Charles E. Garlock, in a field survey on July 13, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO survey date: April 15, 1825 by S Sibley, DS
 GLO witnesses: Aspin 14-S88E-1.24 ch
 WO 14-S89W-1.73 ch

See additional data on rear of sheet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found concrete monument set by Lyle W Munsell for corner of plats: Assessor's Plat No. 9 and Northland. both in the City of Howell

**SURVEY &
 REMONUMENTATION**

SEP 26 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11: North 1/4 cor. Sec. 36 T3N-R4E, Howell Twp. Liv.Co. MI
 set Liv.Co. Remon. brass cap on top of found concrete mon.
 N'ly-0.75'±-Carsonite post
 S65E-79.63'-sp & tag S/s 24" Oak
 S45E-85.56'-sp & tag N/s 30" Oak
 S25W-71.67'-sp & tag W/s of N'ly 14" Box Elder
 N5W-98.75'-sp & tag E/s 12" Elm



Signed by Charles E. Garlock

Date August 19, 1994

Surveyor's Michigan License No. 14762