

SURVEY & REMONUMENTATION

OCT 21 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED 9
 MAY 30 3 46 PM '96
 NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI
 48843

SECTION

For corners in

Livingston Located In: Corner Code M-10
(County)

1. Public Land Survey T 3N R 4E _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

L.S.C. #532m
Register of Deeds Stamp & File Number

I, Charles E Garlock, in a field survey on May 21, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 GLO survey dated April 15, 1825 by S Sibley DS
 GLO witnesses:.....WO 12-N27W-87 lks
 WO 11-N81½W-72 lks

Additional historical survey data on rear of sheety
 B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 3/4" I. Pipe inside 1 1/4" I. Pipe, dug down about 24" and 1 1/4" I. Pipe still could not be pulled to replace.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 M-10: E 1/4 cor. Sec. 25 T3N-R4E, Howell Twp. Liv. Co. MI. drowe found 3/4" I. Pipe down in the larger 1 1/4" I. Pipe far enough to fit 2 6" sections of 1 1/4" I. Pipe on top to point -0.5' and cemented all together with Liv. Co. Remon brass cap on top. Corner is in the Southerly grass shoulder of M-59
 South-2.68'-W 1/4 cor. Sec. 30 T3N-R5E
 S44W-63.01'-sp & tag N/s 42" Oak
 S43E-85.45'-sp & tag N/s 40" Ash
 N8E-128.08'-sp & tag W/s 42" Oak
 N14E-64.95'-sp & tag W/s 30" oak
 North-24.51'-constr. ctr. line of M-59

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 3-6-96, CO. REP JED

Signed by Charles E Garlock Date May 23, 1996
 Surveyor's Michigan License No. 14762