

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED
 DEC 22 9 27 AM '93
 NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI
 48843

For corners in

LIVINGSTON

(County)

Located In:

Corner Code #

- | | | | | | | |
|------------------------------------|---|-----------|---|-----------|------------|-------|
| 1. Public Land Survey | T | <u>3N</u> | R | <u>5E</u> | <u>A-1</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

L.S.C.# 75m

Register of Deeds Stamp & File Number

I, DONALD G. RICHARDS, in a field survey on October 19, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

White Oak 14 N 27 E 44
 White Oak 16 S 64 W 61

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													


SURVEY &
 REMONUMENTATION

1993

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Iron Rod



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Re-set with 1 1/4" x 36" iron pipe w/brass cap stamped "Livingston County Remonumentation Corner"
 S 35 W 63.12' 1" iron reference pipe w/brass cap stamped "Livingston County Witness Point"
 N 45 W 49.08' 1" iron reference pipe w/brass cap stamped "Livingston County Witness Point"
 N 40 E 54.06' nail/LCWT* in W face 24" Maple
 S 45 E 60.11' 1" iron reference pipe w/brass cap stamped "Livingston County Witness Point"
 (* Livingston County Witness Tag)

Signed by DONALD G. RICHARDS  Date December 10, 1993

Surveyor's Michigan License No. 24614
 Corner M-13 T4N-R4E APPROVED by Livingston County Monumentation
 Peer Group 11-23-93