

SURVEY & REMONUMENTATION

FEB 25 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

SECTION
LIVINGSTON
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 3 N R 5 E I-04
T R
T R
T R
- 2. Property Controlling in Section δ T R
 δ T R
- 3. Miscellaneous Property in Sec. δ T R
 δ T R

1998 OCT 20 P 1:21

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

LSC 920M

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat. _____
- 5. Private Claims _____

1. MARY A. BARNWELL in a field survey on AUGUST 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO 5/29/1823 BY SIBLEY
W. OAK 18 S 21 W 32 LKS (21.1')
W. OAK 18 S 67 E 70 LKS (46.2')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A RAILROAD SPIKE WITH A CHISLED "X" 1.5 FEET EAST OF THE CENTERLINE OF ARGENTINE ROAD (PAVED). THIS CORNER POSITION AGREES WELL WITH WITNESSES OF RECORD SINCE 1973.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-04 EAST 1/4 CORNER SECTION 10 / WEST 1/4 CORNER SECTION 11, T3N, R5E OCEOLA TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN:
RESET THE FOUND RAILROAD SPIKE WITH 1 1/4" X 36" BREAKAWAY STEEL PIPE WITH LIVINGSTON COUNTY REMONUMENTATION BRASS CAP WITH SURVEYOR #35999 IN MONUMENT BOX 1/2 FOOT BELOW THE SURFACE OF ROAD.

- S80°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN NORTH SIDE 10" RED PINE 30.04'
- S28°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN NORTH SIDE UTIL. POLE 65.80'
- S54°W NAIL WITH LIVINGSTON COUNTY REMON TAG IN EAST SIDE 14" RED PINE 44.82'
- N20°W NAIL WITH LIVINGSTON COUNTY REMON TAG IN SOUTH SIDE 10" FENCE POST 84.15'

Signed by [Signature]

Date 10/1/98

Surveyor's Michigan License No. 33971



PA. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 7-15-98, CO. REP JED

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JULY 28, 1991
DESIGNED BY ASIS
REVISED JULY 1998
REVISED OCT. 1998