

SURVEY & REMONUMENTATION

FEB 25 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T3N R5E</u>	<u>1-06</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	§ <u> </u> T <u> </u> R <u> </u>	<u> </u>
	§ <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	§ <u> </u> T <u> </u> R <u> </u>	<u> </u>
	§ <u> </u> T <u> </u> R <u> </u>	<u> </u>

1998 OCT 20 P 1:21

NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI.
 48843

LSC 924M

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

MARY A. BARNWELL, in a field survey on AUGUST 17, 1998, do hereby state that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO 5/29/1823 BY SIBLEY
 W. OAK 26 S 62 W 8 LKS (5.3')
 B. OAK 10 N 25 E 23 LKS (15.2')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 1/2" STEEL REROD 4.5 FEET EAST OF THE CENTERLINE OF ARGENTINE ROAD (PAVED) WITH FENCE LINES TO THE WEST AND EAST. THIS CORNER POSITION WAS APPARENTLY ESTABLISHED IN 1992 AND HAS BEEN USED FOR SURVEYS SUBSEQUENT TO THAT DATE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-06 WEST 1/4 CORNER SECTION 14 / EAST 1/4 CORNER SECTION 15, T3N, R5E OCEOLA TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN:
 RESET THE FOUND 1/2" STEEL REROD WITH 1 1/4" X 36" BREAKAWAY STEEL PIPE WITH LIVINGSTON COUNTY REMONUMENTATION BRASS CAP WITH SURVEYOR #35999 IN MONUMENT BOX 1/2 FOOT BELOW THE SURFACE OF ROAD.

N84°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN SOUTH SIDE 6" FENCE POST 29.91'
 S19°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN EAST SIDE 9" HICKORY 90.39'
 N75°W NAIL WITH LIVINGSTON COUNTY REMON TAG IN NORTH SIDE 30" HICKORY 38.79'
 N26°W NAIL WITH LIVINGSTON COUNTY REMON TAG IN EAST SIDE 12" OAK 97.07'

Signed by Mary A. Barnwell
 Surveyor's Michigan License No. 33971

Date 10/1/98



FORM APPROVED BY MICHIGAN BOARD OF PROFESSIONAL SURVEYORS, JULY 28, 1995
 DESIGNED BY 10/95
 DESIGNED JNL, ESB
 DESIGNED OCT, 1995