

**SURVEY & REMONUMENTATION**

FEB 25 1999

FILED

SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

1998 OCT 20 P 1:21

<u>LIVINGSTON</u> (County)	located in:	Corner Code #
1. Public Land Survey	<u>T 3 N R 5 E</u>	<u>I-07</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	§ <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	§ <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	§ <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	§ <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

HANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

LSC 925M

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARY A. BARNWELL, in a field survey on AUGUST 17, 1998 do hereby state that under requirements of D.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5			4		3		2		1		
3													
4	7	8			9		10		11		12		
5													
6	13	17			16		15		14		13		
7													
8	19	20			21		22		23		24		
9													
10	30	29			28		27		26		25		
11													
12	31	32			33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO 5/29/1823 BY SIBLEY  
W. OAK 18 N 81 E 31 LKS (20.5')  
W. OAK 8 S 10 W 17 LKS (11.2')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 1/2" STEEL PIPE IN A MONUMENT BOX 5 FEET SOUTH OF THE INTERSECTION OF ARGENTINE ROAD (PAVED) WITH BROPHY ROAD (GRAVEL). THERE IS A FENCE LINE TO THE WEST. THIS CORNER POSITION AGREES WITH WITNESSES BACK TO 1963.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-07 CORNER COMMON TO SECTIONS 14, 15, 22 AND 23, T3N, R5E OCEOLA TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN:  
RESET THE FOUND 1/2" STEEL PIPE WITH 1 1/4" X 36" BREAKAWAY STEEL PIPE WITH LIVINGSTON COUNTY REMONUMENTATION BRASS CAP WITH SURVEYOR #35999 IN MONUMENT BOX 1/4 FOOT BELOW THE SURFACE OF ROAD.

N82°W NAIL WITH LIVINGSTON COUNTY REMON TAG IN NORTH SIDE 8" HICKORY	50.67'
N68°W NAIL WITH LIVINGSTON COUNTY REMON TAG IN NORTH SIDE 12" HICKORY	52.62'
N49°E SOUTHWEST CORNER OF HOUSE	153.84'
S69°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN EAST SIDE 6" CHERRY	75.21'



Signed by Mary A. Barnwell

Date 10/1/98

Surveyor's Michigan license No. 33971

PA. 245 1990, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 7-15-98 CO. REP JEO

FORM APPROVED BY MICHIGAN DIVISION OF PROFESSIONAL REGULATIONS, JULY 25, 1990  
REVISED MAY 1995  
REVISED APR. 1990  
REVISED OCT. 1995