

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>5E</u>	<u>I-09</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1999 NOV 22 A 10:08

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

LSC# 1085m

Register of Deeds Stamp & File  
Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, MARY A. BARNWELL, in a field survey on SEPTEMBER 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-09 Oceola Township was set by the GLO in 1823.  
The original witnesses are:  
B. Oak 12" S. 34° W. 43 (28.4')  
B. Oak 12" S. 68 1/2° E. 47 (31.0')

NOTE: None of the original witnesses could be found or perpetuated.  
See the back of this sheet for additional historical data.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-09 Found 1/2" Iron Rod in Monument Box 4 feet North of the pavement centerline of M-59 in the centerline of Argentine Road (asphalt surface North -gravel surface South)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-09 Southeast Corner, Section 22, T3N, R5E - Set Brass Cap marked as "Livingston County Monumentation Corner" on existing 1/2" Iron Rod in Monument Box

- N 42° W 88.72' Set Nail/Remon Washer NE/S 14" Maple
- S 45° W 72.14' Set Witness Pipe W/Brass Cap Marked "Livingston County Remonumentation Witness"
- S 50° E 108.76' Set Witness Pipe W/Brass Cap Marked "Livingston County Remonumentation Witness"
- N 48° E 151.74' Set Nail/Remon Washer S/S 18" Hickory
- N 09° E 138.39' Set Nail/Remon Washer W/S 18" Hickory

Signed by Mary A. Barnwell  
Surveyor's Michigan License No. 33971



11-4-99

PA. 3-15 1990, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 9-15-99 CO. REP JED

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995