

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

1999 NOV 22 A 10:08

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

T.S.C# 1086m
Register of Deeds Stamp & File
Number

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>5E</u>	<u>I-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, MARY A. BARNWELL, in a field survey on SEPTEMBER 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-10 Oceola Township was set by the GLO in 1823.
The original witnesses are:
White Oak 8" N. 56° W. 10 (6.6')
White Oak 6" N. 49° E. 19 (12.5')

NOTE: None of the original witnesses could be found or perpetuated.
See the back of this sheet for additional historical data.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10 Found 1/2" Iron Rod at the centerline of Argentine Road (gravel surface running North/South) old fence Running East - old fence running West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10 West 1/4 Corner, Section 26, T3N, R5E - Reset 1/2" Iron Rod with 36"x1 1/4" Breakaway Iron Pipe W/Brass Cap marked as "Livingston County Monumentation Corner"

N 42° W Nail/Remon Washer NE/S 18" Oak 29.42'
N 46° E Nail/Remon Washer SE/S 8" Hickory 38.50'
N 52° E Nail/Remon Washer NE/S 22" Oak 23.07'
S 44° W Nail/Remon Washer SE/S 18" Oak 49.07'

Signed by Mary A. Barnwell

Surveyor's Michigan License No. 33971



11-4-99

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 9-1-99 CO. REP JED

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995