

**SURVEY & REMONUMENTATION**

FEB 25 1999

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**FILED**

For corners in

**SECTION**

1998 OCT 20 P 1:21

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

LSC926M

Register of Deeds Stamp & File Number

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T 3 N R 5 E</u>	<u>J-07</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	§ <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	§ <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	§ <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	§ <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARY A. BARNWELL, in a field survey on AUGUST 17, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

GLO 5/29/1823 BY SIBLEY  
W. OAK 15 S 26 1/2 E 32 LKS (21.1')  
W. OAK 10 N 29 E 31 LKS (20.5')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 5/8" STEEL REROD 2 FEET NORTH AND 2 FEET WEST OF THE INTERSECTION OF BOTTSFORD ROAD AND BROPHY ROAD (BOTH GRAVEL). THERE IS A FENCE LINE TO THE NORTH. THIS CORNER POSITION AGREES WITH WITNESSES BACK TO 1963.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**J-07 SOUTH 1/4 CORNER SECTION 14 / NORTH 1/4 CORNER SECTION 23, T3N, R5E OCEOLA TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN:**  
**RESET THE FOUND 5/8" STEEL REROD WITH 1 1/4" X 36" BREAKAWAY STEEL PIPE WITH LIVINGSTON COUNTY REMONUMENTATION BRASS CAP WITH SURVEYOR #35999 1/2 FOOT BELOW THE SURFACE OF THE ROAD.**

N05°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN WEST SIDE 18" ELM 31.78'  
N68°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN SOUTH SIDE 60" OAK 38.31'  
S64°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN NORTH SIDE 16" LOCUST 67.32'  
S53°W NORTHEAST CORNER OF HOUSE AT CONCRETE FOUNDATION 100.01'

Signed by [Signature]

Date 10/1/98

Surveyor's Michigan License No. 33971



PA. 345 1880, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 7-15-98 CO. REP JED

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, LANSING, MI 48201  
DESIGNED BY 1956  
REVISED JUL 1988  
REVISED OCT 1995