

SURVEY & REMONUMENTATION

FEB 26 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

|                                       |                           |               |
|---------------------------------------|---------------------------|---------------|
| <u>LIVINGSTON</u><br>(County)         | Located In:               | Corner Code # |
| 1. Public Land Survey                 | T <u>3</u> N R <u>5</u> E | <u>C-11</u>   |
|                                       | T ___ R ___               | _____         |
|                                       | T ___ R ___               | _____         |
|                                       | T ___ R ___               | _____         |
| 2. Property Controlling<br>in Section | S ___ T ___ R ___         | _____         |
|                                       | S ___ T ___ R ___         | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S ___ T ___ R ___         | _____         |
|                                       | S ___ T ___ R ___         | _____         |

2000 AUG 29 A 9:30

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

LSC #1257m

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |

I, CHARLES E. GARLOCK, in a field survey on JULY 10, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1823 S. SIBLEY SET POST  
WHITE OAK 13° N 10° E 5.28'  
WHITE OAK 7° S 68° E 3.96'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON ROD ON THE PROJECTED CENTERLINES OF THE ROADS WEST AND SOUTH. THE 1/2" IRON IS ALSO IN LINE WITH THE REMAINS OF A FENCE LINE TO THE EAST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11 SOUTHWEST CORNER SECTION 29, T3N, R5E, OCEOLA TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN:  
SET 1 1/4" X 36" STEEL PIPE WITH LIVINGSTON COUNTY REMONUMENTATION BRASS CAP STAMPED WITH SURVEYOR #14762 IN PLACE OF THE 1/2" IRON ROD.

|                              |        |
|------------------------------|--------|
| EAST SP&TAG S/S 3-16" OAKS   | 11.14' |
| S85°E SP&TAG N/S 16" OAK     | 32.20' |
| S40°E SP&TAG W/S 3- 15" OAK  | 34.49' |
| N45°W SP&TAG E/S 20" HICKORY | 36.16' |



Signed by Charles E. Garlock

Date 7-21-00

Surveyor's Michigan License No. 14762