

MAR 17 2000

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1999 JUL 29 P 12: 27

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

For corners in

LIVINGSTON

(County)

Located In:

Corner Code #

1. Public Land Survey	T3N R6E	F-9
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

CLS # 1044m

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, CHARLES E GARLOCK, in a field survey on JULY 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													


A. Description of original monument and accessories and/or subsequent restoration:  
GLO SURVEY DATED: MAY 24, 1823 BY S SIBLEY AND NONE OF THE GLO WITNESSES REMAIN.  
GLO WITNESSES WO 10-N71 1/2 W-68.64'  
BO 18-S13E-124.74'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND 1/2" IRON ROD

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
F-9: N 1/4 COR. SEC. 28 T3N-R6E, HARTLAND TWP. LIV. CO. MI. RESET 1/2" I. ROD WITH 1 1/2" X 36" I. PIPE WITH LIV. CO. REMON. BRASS CAPON TOP  
SOUTH-31.51' - "T" IRON AND CAP  
S45E-64.06' - C/L 2" STEEL POST  
N10E-82.13' - SP & TAG E/S U. POLE  
N35E-136.25' - SP & TAG S/S U. POLE  
N45W-136.87' - SP & TAG S/S U. POLE  
W'LY-16.1' - NEAREST EDGE OF ASPHALT EXIT RAMP

Signed by Charles E. Garlock  
Surveyor's Michigan License No. 14762

Date JULY 19, 1999



PA. 345 1990, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 5-5-1999 CO. REP JED