

FEB 25 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LIVINGSTON

(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|-------------------------|-----------|
| 1. Public Land Survey | T <u>3N</u> R <u>6E</u> | <u>G6</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

1998 OCT 20 P 1:21

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

LSC931M

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARY BARNWELL, in a field survey on AUG 20, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


GLO SURVEY DATED MAY 24, 1823 BY S SIBLEY AND NONE OF THE GLO WITNESSES REMAIN.
GLO WITNESSES: W015-S63½E-20.46'
W010-N10E-26.40'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" I. ROD NE CORNER OF 12" WOOD POST SET IN STONES, WITH FENCE LINES SOUTH, EAST AND WEST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G6: W 1/4 COR. SEC. 15, T3N-R6E HARTLAND TWP. LIV. CO. MI., REPLACED 1/2" I. ROD WITH 1 1/4" X 36" I. PIPE WITH LIV. CO. REMON. BRASS CAP ON TOP.
S75E-16.55'-SP & TAG N/S 30" OAK
S35E-29.56'-SP & TAG W/S 24" OAK
SOUTH-54.91'-SP & TAG E/S 14" OAK
S80W-34.12'-SP & TAG S/S OF 5 MULTI-OAKS 50" IN DIA.

Signed by 
Surveyor's Michigan License No. 33971

Date AUGUST 21, 1998



PA. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 8-19-98 CO. REP VED