

MAR 17 2000

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE JUL 29 P 12:27  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LIVINGSTON (County)	Located In:	Corner Code #
1. Public Land Survey	T 3N R 6E	H11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

cls# 1047m

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, CHARLES E GARLOCK, in a field survey on MAY 11, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	5		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

GLO SURVEY DATED: MAY 24, 1823 BY S SIBLEY AND NONE OF THE GLO WITNESSES REMAIN  
GLO WITNESSES: MAPLE 6-N23 1/2 W-7.26'  
ASPEN 14-S22E-42.90'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A CONCRETE MONUMENT WITH PIPE ON NORTH BANK OF AN EAST-WEST DRAIN AND ABOUT 11 FT. SOUTH OF AN EAST-WEST TRAIL.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H11: S 1/4 COR. SEC. 27 T3N-R6E, HARTLAND TWP. LIV. CO. MI. SET 1/2" X 18" I. ROD INSIDE 3/4" I. PIPE ENCASED IN FOUND CONC. MON. AND ATTACHED LIV. CO. REMON BRASS CAP TO THE TOP WITH NO. 14762  
NORTH-43.72'-SP & TAG E/S 18" ELM  
N35E-40.17'-SP & TAG E/S 14" MAPLE  
N55W-62.09'-SP & TAG SW/S 24" OAK  
S88W-61.48'-SP & TAG N/S 15" ASH  
NORTH-11'-C/L TRAIL  
SOUTH-11'-C/L DITCH

Signed by Charles E. Garlock  
Surveyor's Michigan License No. 14762

Date MAY 25, 1999

