


K-13 - SOUTHWEST CORNER SECTION 36, T3N, R6E, HARTLAND TOWNSHIP

SUMMARY:

Boss Engineering did a survey in July 1972 which shows the Southwest Corner. This corner appears to match the location called for as the Northwest Corner of Section 1, Brighton Township in a survey for the General Motors proving grounds. There is a 1" iron shaft as set for GM at the location now. The iron falls approximately 1 foot south of the centerline of Commerce Road and is approximately on a tree row going to the north. The GLO falling would put the Southwest Corner 35.64 feet east of the Northwest Corner of Section 1 Brighton although no "jog" is apparent. There is no occupation to the south due to the proving grounds, although the worksheet for the proving grounds survey does show fence going south. This Corner location has been used by Don Ross, Boss Engineering, and in-process work by Desine. No other irons were found in a search of the area. I recommend accepting the Southwest Corner at the location as is presently monumented.




Jack K. Smith, PS