

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OCT 17 10 33 AM '95
 NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY MI
 48843

FILED

or corners in			
<u>LIVINGSTON</u>	Located In:	Corner Code #:	
(County)			
Public Land Survey	T <u>3N</u> R <u>6E</u>	<u>L-07</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
Property Controlling	S _____ T _____ R _____	_____	
in Section	S _____ T _____ R _____	_____	
Miscellaneous	S _____ T _____ R _____	_____	
Property in Sec.	S _____ T _____ R _____	_____	

L.S.C.# 506m
 Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

Jack K. Smith, in a field survey on October 10, 19 95,
 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.

Description of original monument and accessories and/or subsequent restoration:
 L-07 The North 1/4 Corner of Section 24, Hartland Township was set by the
 GLO in 1823 by S. Sibley.
 The original witnesses are:
 W Oak 7" S10°E 39 lk (25.7')
 W Oak 6" N10°E 38 lk (25.1')

NOTE: NONE OF THE ORIGINAL WITNESSES COULD BE FOUND OR PERPETUATED
 SEE THE BACK OF THIS SHEET FOR ADDITIONAL HISTORICAL DATA.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 L-07 Found 1/2" iron on the centerline of Dunham Road.

SURVEY &
 MONUMENTATION
 NOV 27 1995
 COMMISSION




Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 L-07 North 1/4 Corner, Section 24, T3N, R6E
 Set 30" x 1 1/4" iron pipe with 6" x 1 1/4" break-off and brass cap marked
 as "Livingston County Monument Corner".
 N60°E Set nail and tag in NW side 26" Oak 59.47'
 S14°E Set nail and tag in W side 16" Maple 21.54'
 S72°W Set nail and tag in SE side 14" Cherry 44.13'
 N38°W Set nail and tag in NE side 18" Maple 30.53'

Signed by Jack K. Smith Date October 15, 1995
 Surveyor's Michigan License No. 35999

June 20, 1995

L-07 T3N - R6E: NORTH 1/4 CORNER, SECTION 24, HARTLAND TOWNSHIP

We found a 1/2" iron on the centerline of Dunham Road (gravel) with occupation to the south. The corner was originally recorded as being set by S. Sibley in 1823. This corner is shown on a survey from 1878/1879 by Teller with one witness (now gone) in which he calls for the setting of the corner. There is a note in the margin of the document that states "made a resurvey.....I found the 1/4 post on the South line". On notes of Dunning from 1916 he states that he found "S 1/4 post stone" as set by Teller. In 1968 Charles Garlock shows a found "T" iron bent and replaced it with a 1/2" iron. The witnesses for this corner match well from 1980 to the present. We dug up this re-rod to look for evidence of the Teller "stone" and found that the iron is placed about 1/2 foot northwesterly of a rock that is about 2'x3'x2' with no discernable point. It looks too big to be used for the corner and many usable rocks are available in the area, but it could possibly have been intended to mark the corner. A sweep of the area did not reveal any additional irons. This corner is wooded and would be difficult for GPS occupation. I recommend accepting L-07, the North 1/4 Corner of Section 24, at the location as is presently monumented.


Jack K. Smith, PS
Desine Inc.

