

9-

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

LIVINGSTON  
(County)

Located in:

Corner Code #

1996 NOV 14 P 1:22

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

L.S.C.#589m

Register of Deeds Stamp & File Number

1. Public Land Survey	T <u>4N</u> R <u>3E</u>	B-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9	●											
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

CONWAY

I, DARRELL HUGHES, in a field survey on 10-29, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
GLO: 1825  
White Ash 8", South 4 degrees West, 7 links  
Black Ash 17", North 29 degrees East, 32 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 1/2" smooth iron rod

\*Additional historical information on back of this sheet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
B-9, T4N, R3E, CONWAY, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful perpetuation of the position of the original corner.  
081 DEG. 115.78' SET NAIL/TAG S/S 60" MAPLE.  
316 DEG. 31.29' SET NAIL/TAG SW/S 24" TWIN ELM STUMP.  
030 DEG. 42.07' SET NAIL/TAG W/S 15" ELM.  
116 DEG. 54.88' SET NAIL/TAG N/S 4" SUMAC.  
191 DEG. 18.13' SET NAIL/TAG TOP CENTER, WEST END 12" CMP CULVERT.

Signed by Darrell Hughes  
Surveyor's Michigan License No. 19834

Date October 29, 1996

CONWAY TOWNSHIP, T4N, R3E

B-9, NORTH 1/4 CORNER SEC. 30 AND SOUTH 1/4 CORNER SEC. 19.

FIELD 6-20-1996 DARRELL D. HUGHES AND ASSOCIATES, FOWLerville.

Found 1/2" smooth iron rod 0.3' below centerline of gravel road grade. On fence line to North. 6.5' West of field line to South. Measures East to C-9 check with 1980 Boss measurement. Witness' also agree with 1980 Boss survey (P.11). I recommend, to the peer group, the acceptance of this location for B-9. Location OK for GPS.

1825 Sylvester Sibley, Deputy U.S. Surveyor, "West between 19 and 30....40.00 chains, set 1/4 section post."

1871 Miles Bullock re-establishes corner 2657.16' West of C-9. (P.8)

1872 Miles Bullock resets corner 2652.54' West of C-9. (P.9)

1980 Gary Boss, in a survey, does not say if "1/2 iron" is found or set. Measures 2658.59' East to C-9. (P.11)

1990 Ed Jacobs uses corner in survey and gives no witness' and does not identify physical corner. Measures East 2657.49' to C-9. (P.12)  
P.S. I called JCK Associates. Mr. Jacobs passed away and no witness' shown in field notes. (P.12)

1994 Hughes survey witness' for corner agree with 1980 Boss survey. (P.13-14)