

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

9-
FILED

For corners in

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>3E</u>	<u>B-13</u>
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

1996 NOV 14 P 1:22

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L. S. C. #591m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DARRELL HUGHES, in a field survey on 10-29, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

CONWAY

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825
Maple 7", North 79 degrees East, 13-1/2 links
Maple 13", North 25-1/2 degrees West, 48-1/2 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod, set remonumentation pipe 0.20 ft. West of 1/2" rod on C-13/B-1 line. Removed iron rod.

*Additional descriptions and historical information on back of this sheet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13, T4N, R3E, CONWAY, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful perpetuation of the position of the original corner.
360 DEG. 35.98' SET NAIL/TAG E/S 20" OAK.
315 DEG. 51.53' SET NAIL/TAG SW/S 12" OAK.
270 DEG. 40.60' SET NAIL/TAG S/S 22" OAK.
175 DEG. 83.36' SET NAIL/TAG NE/S UTILITY POLE.
085 DEG. 14.00' FD. 1/2" IRON ROD/CAP 17022.

Signed by [Signature]
Surveyor's Michigan License No. 19834

Date October 29, 1996



CONWAY TOWNSHIP, T4N, R3E

B-13, THE SOUTH 1/4 CORNER SECTION 31, ON THE TOWNSHIP LINE.

FIELD: 6-24-1996 DARRELL D. HUGHES AND ASSOCIATES, FOWLERVILLE.
9-17-1996 FIELD CHECK 1980 BOSS WITNESS'

Found 1/2" iron rod 1.5' South of fence corner post. Fence to North and West. 1980 Boss witness' check to fence post, no nails found in trees. Measures check East to B-1, Handy. +/- 0.15' Measures East to C-13 0.24' short. The 1/2" iron now falls on the B-1 & C-13 line. I recommend, to the peer group, setting B-13 0.20' West to match B-1 and C-13 and on the C-13/B-1 line extended, as it now stands. Poor for GPS.

1824 Joseph Wampler, Deputy U.S. Surveyor, "West on the South boundary of Section 31, 40.00 chains, set 1/4 section post". P.7-7B

1980 Boss "Lady Jane Lake" survey shows relationship with B-1, Handy. P.8-8B

1988 Boss survey using corner. Measures West to A-13 1801.07', GLO 1805.76' P.9-9A

1990 Brady survey. Copies Boss witness' P.10-10A

1995 Witness comparison list. P.11