

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

9-
FILED

For corners in

| | | |
|---------------------------------------|--|---------------|
| <u>LIVINGSTON</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>4N</u> R <u>3E</u> | <u>C-12</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

1996 NOV 14 P 1:20
 NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI.
 48843

L.S.C.#570m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, DARRELL HUGHES, in a field survey on 10-29, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

CONWAY

A. Description of original monument and accessories and/or subsequent restoration:
 GLO: 1825
 Black Ash 8", South 17 degrees West, 29 links
 Tamarack 19", North 77-1/2 degrees East, 9 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1/2" iron rod


*Additional descriptions and historical information on back of this sheet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-12, T4N, R3E, CONWAY, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful perpetuation of the position of the original corner.
 233 DEG. 53.04' SET NAIL/TAG E/S TWIN MAPLE.
 274 DEG. 38.94' SET NAIL/TAG S/S 10" MAPLE.
 313 DEG. 51.31' SET NAIL/TAG NE/S QUAD. MAPLE.
 091 DEG. 55.26' SET NAIL/TAG S/S 16" MAPLE.

Signed by Darrell Hughes
 Surveyor's Michigan License No. 19834

Date October 29, 1996



CONWAY TOWNSHIP, T4N, R3E

C-12, THE EAST 1/4 CORNER OF SECTION 31 AND THE WEST 1/4 CORNER OF SECTION 32.

FIELD: 6-21-1996 DARRELL D. HUGHES AND ASSOCIATES, FOWLerville.

Found 1/2" iron rod 0.3' below gravel road grade in centerline of Stow Road. After research at the county court house and requesting information from some 36 surveyors, the earliest recent evidence of witnessing is 1993 (South 1168.99 feet to 1-1/2" iron pipe centerline of Stow and Allen Roads). However, iron is at centerline of physical road and on line with E/W fence to West. Measures North to C-11 are close to 2640'. Measures South to C-13 agree with Garlock. I recommend the acceptance of this iron, to the peer group, for the position of C-12. Poor for GPS.

- 1825 Sylvester Sibley, Deputy U.S. Surveyor, "North between 31 and 32, 40.00 chains, set 1/4 section post". P.7-7A
- 1895 Miles Bullock witness. (tree now gone) P.8
- 1990 Garlock survey. (no witness' shown) P.9
- 1990 Brady survey. (no witness' shown) P.10-10A
- 1993 Garlock survey. (one witness 1168.99' south to iron pipe) P.11
- 1994 Hughes survey. find two Brady accessories and set new witness'. P.12-12B
- 1995 Garlock measures township line for 1995 remonumentation. shows distance from C-12 to C-13. P.13
- 1996 Witness comparison list. P.14