

**SURVEY &
REMONUMENTATION**

FEB 25 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

FILED

For corners in

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>3E</u>	<u>D9</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

91
1998 AUG 20 P 4:45
NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843
L.S.C. #881m
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, CHARLES E GARLOCK, in a field survey on JULY 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9				29		28		27		26		25	
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY, DS
GLO WITNESSES: IRONWOOD 7-N28E-8 LKS
WO 28-N83W-35 LKS



ADDITIONAL DATA ON REAR OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND "T" IRON ON CENTERLINE OF GRAVEL ROAD WITH OCCUPATION OF SMALL ROW OF TREES TO SOUTH AND STONE PILED IN TREE ROW.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D9: N 1/4 COR. SEC. 29, T4N-R3E, CONWAY TWP. LIV. CO. MI, RESET FOUND "T" IRON WITH 1 1/2" X 36" BREAKAWAY I. PIPE WITH LIV. CO. REMON BRASS CAP ON TOP AT -0.5'
S11E-38.70'-SP & TAG E/S 8" ELM
S6E-31.54'-SP & TAAG E/S 5" OAK
S7W-35.37'-PK SPIKE CEMENTED IN HIGHEST POINT OF ROCK 3' X 4' & 1' HIGH
S10W-39.60'-SP & TAG W/S 8" OAK

Signed by Charles E. Garlock Date AUGUST 8, 1998
Surveyor's Michigan License No. 14762

PA. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 2/11/98 CO. REP JED