

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

9-
FILED

For corners in

LIVINGSTON Located In: Corner Code #
(County)

1. Public Land Survey T4N R 3E D-13
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

1995 NOV 14 P 1:20

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C.#571m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DARRELL HUGHES, in a field survey on 10-24, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

CONWAY

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825
Maple 6", North 39 degrees West, 8 links
Elm 7", North 55 degrees East, 18 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1-1/4" iron pipe with brass cap #14762 set by Garlock in 1995 Remonumentation project.

*Additional descriptions and historical information on back of this sheet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13, T4N, R3E, CONWAY, found and accepted existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 14762, and is accepted as a careful and faithful perpetuation of the position of the original corner.
090 DEG. 166.59' D-1, T3N, R3E, HANDY.
270 DEG. 4.67' FD. NAIL/REMON.TAG S/S 6" ELM.
360 DEG. 57.55' FD. NAIL/REMON.TAG E/S 15" ASH.
045 DEG. 30.52' FD. NAIL/REMON TAG W/S TRIPLE 12" MAPLE.
090 DEG. 29.27' FD. NAIL/REMON TAG N/S TWIN 15" POPLAR.

Signed by Darrell Hughes
Surveyor's Michigan License No. 19834

Date October 24, 1996

CONWAY TOWNSHIP, T4N, R3E

D-13, THE SOUTH 1/4 CORNER OF SECTION 32, ON THE TOWN LINE.

FIELD: 6-21-1996 DARRELL D. HUGHES AND ASSOCIATES, FOWLerville.

Found 1-1/4" Iron pipe in E/W fence line as set by Garlock in 1995. As stated in Garlock's Act 74, "Set iron pipe at half distance between C-13 and E-13 and on E/W fence line." P.8C Garlock, then being the monumenting surveyor for Conway Township, had to resolve the position of E-13 by running out the South township line West to C-13. No evidence of this corner ever being used by any surveyor. No occupation North. An 1/2" iron was found by Garlock 18.62' West of this position, in the E/W fence line. The North 1/4 corner of Sec. 5 (D-1) Handy, as proposed by Garlock, See drawing P.8C, is 166.59' East (computed GLO= 169.95') I recommend, to the peer group, the acceptance of the method used by Garlock to establish this corner. Our measures West to C-13 agree and Garlock's witness' check. C-13 to G-13, as measured and shown by Garlock (bottom center page 8-B.....10539.3' divided by 4 = 2634.825'), is further weight for the position of this corner.

1825 Sylvester Sibley, Deputy U.S. Surveyor, "West on the South boundary of Sec. 32, 40.00 chains, set 1/4 section post". P.7-7A

1995 Garlock's 1995 remonumentation measures and notes for the establishment of E-13. P.8-8B

1995 Garlock sets D-13 and files Act 74. P.8C