

**SURVEY &
REMONUMENTATION**

FEB 25 1999

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

FILED

For corners in

SECTION

LIVINGSTON
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T <u>4N</u> R <u>3E</u> | E9 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
In Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

91

1998 AUG 20 P 4:45

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C. #882m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, CHARLES E GARLOCK, in a field survey on AUG 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

- A. Description of original monument and accessories and/or subsequent restoration:
 GLO SURVEY DATED: APRIL 15, 1825 BY S SIBLEY, DS
 GLO WITNESSES: SUGAR 8-N66W-20 LKS
 IRONWOOD 6-S75E-5 LKS.



ADDITIONAL DATA ON REAR OF SHEET

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 5/8" I. ROD, LIGHT OCCUPATION TO THE NORTH AND SOUTH, ON CENTERLINE OF GRAVEL ROAD & 5' WEST OF DRIVEWAY TO HOUSE #9490

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 F9: N 1/4 COR. SEC. 28, T4N-R3E, CONWAY TWP. LIV. CO. MI, RESET 5/8" I. ROD WITH 1 1/4" X36" BREAKAWAY I. PIPE WITH LIV. CO. REMON BRASS CAP ON TOP AT -0.5'
 N4E-23.18'-SP & TAG W/S 3' HIGH U POLE
 S17W-25.42'-SP & TAG W/S U POLE
 S75W-82.54'-SP & TAG E/S 12" MAPLE
 N70W-60.07'-SP & TAG E/S 12" DBL MAPLE

Signed by *Charles E. Garlock* Date AUGUST 8, 1998
 Surveyor's Michigan License No. _____

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 2/11/98 CO. REP JED