

SURVEY & REMONUMENTATION

FEB 25 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

LIVINGSTON
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 4N R 3E G9
 T ___ R ___ ___
 T ___ R ___ ___
 T ___ R ___ ___
- 2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___ ___
- 3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___ ___

9/

1998 AUG 20 P 4:45

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C. #884m

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, CHARLES E GARLOCK, in a field survey on JULY 8, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	19	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 GLO SURVEY DATED: APRIL 15, 1823 BY S SIBLEY, DS
 GLO WITNESSES: MAPLE 25-N78½E-20 LKS.
 BEECH 8-S22½W-10 LKS



ADDITIONAL DATA ON REAR OF SHEET

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND ½" I. PIPE AT INTERSECTION OF GRAVEL ROADS CENTERLINE, WHICH WAS USED BY ALL KNOWN SURVEYORS. FOUND A SECOND IRON NNW 5.87 FT., NO WITNESSES MATCHED THIS IRON AND DID NOT FIND ANY SURVEYOR THAT HAD USED IT.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G9: NE COR. SEC. 28, T4N-R3E, CONWAY TWP. LIV. CO. MI, RESET 1/2" I. PIPE WITH 1¼" X 36" I. PIPE WITH BREAKAWAY TOP AND LIV. CO. REMON BRASS CAP ON TOP IN GRAVEL ROAD AT -0.5'
 N29W-91.28'-SP & TAG W/S 7" CHERRY
 N45E-88.30'-SP & TAG W/S 18" ASH
 N65E-89.02'-SP & TAG W/S 14" OAK
 N71W-91.34'-SP & TAG ON 8' HIGH U. POLE
 S31E-135.63'-NW CORNER STORAGE BLDG
 S34E-37.74'-C/L 2" STREET SIGN POST

Signed by Charles E. Garlock
 Surveyor's Michigan License No. 14762

Date JULY 20, 1998

PA. 345 1990, APPROVED BY LIVINGSTON COUNTY
 PEER GROUP ON 2/11/98, CO. REP JED