

FILED

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Nov 10 8 14 AM '94

NANCY HAVILAND REGISTER OF DEEDS LIVINGSTON COUNTY, MI 48843

For corners in LIVINGSTON (County)

Located In: Corner Code ##

Table with 3 columns: Description, Located In (T, R, S), and Corner Code. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

L.S.C.#276m

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column G and row 11.

I, Donald G. Richards, in a field survey on August 13th, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

"West corrected between 27 & 34 40.03 (chains) set post on true line for 1/4 section corner
a White Oak 18 S 29 W 30
a White Oak 7 12 W 23"
Sylvester Sibley, between February 18th and 25th, 1825

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rorod with cap no. 19834 (Darrell D. Hughes) (see reverse side for research and investigation summary)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Reset with 1 1/4" iron pipe w/brass cap stamped "Livingston County Monumentation Corner" and "24614" in Monument Box
SOUTH 14.88' 1" iron witness pipe w/brass cap* at south edge blacktop
N 60 E 44.07' nail/tag** in northwest side 37" oak
N 10 W 20.71' nail/tag** in east side 40" ash
N 70 W 74.43' nail/tag** in south side 8" ash
*cap reads "Livingston County Remonumentation Witness" and is stamped "24614"
**tags read "Livingston County Survey Witness" and are stamped "24616"

Handwritten signature of Donald G. Richards

(approved by peer group 9-21-94)

Signed by DONALD G. RICHARDS

Date October 29, 1994

Surveyor's Michigan License No. 24614