

SURVEY & REMONUMENTATION

FEB 25 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

LIVINGSTON
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 4N R 3E I 9
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

9/

1998 AUG 20 P 4: 45

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C. #878m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, CHARLES E GARLOCK, in a field survey on AUG 5, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9									●				
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO SURVEY DATED: APRIL 15, 1825 BY S SIBLEY, DS
GLO WITNESSES: SYM7-N65W-15 LKS
 SYM6-S62½E-12 LKS

ADDITIONAL DATA ON REAR OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND, 1/2" I. ROD ON CENTERLINE CROSSING IN ASPHALT PVMT. CORNER MATCHES G DUNNING 1915 WITNESS WITH 1.5', MOST OF HIS MEASURES WERE FROM FACE OF TREES
RECENTLY LIV. CO. RD. COMM SET A MON. BOX AROUND THE FD. 1/2" I. ROD



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I9: NE CORNER SECTION 27, T4N-R3E, CONWAY TWP. LIV. CO. MI., RESET FD. 1/2" I. ROD WITH 1½" X 36" I. PIPE WITH BREAKAWAY TOP AND LIV. REMON BRASS CAP ON TOP IN A MON. BOX
N45W-135.51'-SP & TAG S/S 24" POPLAR
N70E-67.72'-SP & TAG S/S U POLE
S80E-64.22'-SP 7 TAG N/S 24" MAPLE
N30W-101.67'-SP & TAG E/S 18" MAPLE

Signed by Charles E. Garlock
Surveyor's Michigan License No. 14762

Date AUGUST 8, 1998