

**SURVEY & REMONUMENTATION**

1993

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

DEC 22 9 24 AM '93

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI  
48843

For corners in

LIVINGSTON  
(County)

Located In:

Corner Code #

- |                                    |                         |             |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey              | T <u>4N</u> R <u>3E</u> | <u>K-13</u> |
|                                    | T _____ R _____         | _____       |
|                                    | T _____ R _____         | _____       |
|                                    | T _____ R _____         | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____       |
|                                    | S _____ T _____ R _____ | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____       |
|                                    | S _____ T _____ R _____ | _____       |

L.S.C. #63m

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Donald G. Richards in a field survey on October 19, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Joseph Wampler, February 14th, 1824  
"Set post corner of Sections 35 & 36 from which a  
White Oak 12" diameter bears N 66 W 44 links distant  
White Oak 9" diameter bears N 52 1/2 E 91 links distant"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Rerod  
(see research side for research and investigation summary)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Re-set with 1 1/4" x 36" iron pipe w/brass cap stamped "Livingston County Remonumentation Corner"  
S 55 W 66.00' nail/LCWT\* in N face 13" Ash  
N 05 W 48.30' nail/LCWT in E face 26" Maple  
N 70 E 120.63' nail/LCWT in S face 36" Maple  
S 60 E 44.97' nail/LCWT in SW face twin 10" Hickory  
EAST 68.04' section corner K-1, T3N-R3E  
(\* Livingston County Witness Tag)



Signed by DONALD G. RICHARDS Date December 10, 1993

Surveyor's Michigan License No. 24614  
PROVED by Livingston County Monumentation Peer Group 11-10-93

CONWAY K-13

This standard corner was first set by Joseph Wampler in the winter of 1824. From county surveyor information provided by Mr. Garlock, this corner was monumented by an iron set by Pat Benton in 1968. These records give a distance of 70.2' East to the closing corner for the adjoining township on the south.

Benton's witnesses and identification were in use for this point until a survey by A.F. Miller in the late 70's. Miller recovers a 1" pipe with rerod. This same identification and three witnesses were utilized by Charles Garlock in recording the corner in 1979.

On October 19, 1993 fieldcrews recovered a 1/2" rerod marking this standard corner. Additionally, one witness tie dating back to Benton'68 was recovered. It's location relative to corners K-12, and L-13 compares favorably with distances noted in surveys by Miller'79 and Garlock'92. The distance to closing corner K-1 is 2.16 Feet shorter than that noted by Munsell'68 but is within 0.04' of distance noted on LSC 686 for corner K-1.

Donald G. Richards PS 24614  
October 22, 1993