

SURVEY & REMONUMENTATION

JUL 16 1997

9

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

LIVINGSTON
(County)

Located In: Corner Code #

1. Public Land Survey

T4N R 3E M-5
T R
T R
T R

2. Property Controlling in Section

S T R
S T R

3. Miscellaneous Property in Sec.

S T R
S T R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1997 MAY 27 P 3:40

HANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C. #662m

Register of Deeds Stamp & File Number

I, CHARLES E GARLOCK, in a field survey on MAY 19, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													


A. Description of original monument and accessories and/or subsequent restoration:
GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY AND NONE OF GLO WITNESSES REMAIN
GLO WITNESSES: LYNN 10"-S35W-34 LKS
BEACH 10"-N38W-8 LKS

ADDITIONAL DATA ON REAR OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FD. FLAT STONE, BROKEN BRICK AND 1/2" I. ROD

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-5:SE CORNER OF SEC. 12, T4N-R3E, CONWAY TWP. LIV. CO. MI., RESET ABOVE WITH 1 1/4" X 36"

- I. PIPE (BREAKAWAY) WITH LIV. CO. REMON. BRASS CAP ON TOP AT -0.5'
- N75E-47.55'-SP & TAG N/S 24" HICKORY
- S36E-49.91'-SP & TAG W/S U. POLE
- S28W-69.32'-SP & TAG W/S 10" PIGNUT HICKORY
- S75W-25.83'-SP & TAG N/S 18" HICKORY
- SOUTH-5'-C/L ROAD TO EAST
- EAST-3'-C/L ROAD TO N. & S.
- NORTH-7.26'-T4N-R4E SEC. CORNER



Signed by Charles E. Garlock
Surveyor's Michigan License No. 14762

Date MAY 20, 1997

P.A. 345 1980, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 2/5/1997 CO. REP JED

SERVING LIVINGSTON COUNTY
SINCE 1868

"Be Sure of Your Ground"

CHARLES E. GARLOCK

PROFESSIONAL SURVEYOR

705 N. MICHIGAN AVE.

HOWELL, MICHIGAN 48843

OFFICE: (517) 546-3340

FAX: 517 546-2941

DECEMBER 28, 1996

M-5: SE CORNER OF SECTION 12, T4N-R3E, CONWAY TWP. LIV. CO. MI

GLO SURVEY DATED APRIL 15, 1825 BY S. SIBLEY, DS, AND NONE OF THE GLO WITNESSES REMAIN.

THIS IS A DOUBLE CORNER AGAIN. IN 1975 K PIOTROWSKI FOUND A 1/2" I. ROD AND PLACED HIS CAP ON TOP; BUT IN 1982 D HUGHES FOUND A FLAT STONE ON END W/BRICK AND CROCKERY AROUND THE STONE AND ALSO FOUND A CAST IRON PUMP NOZZLE 7.26 FEET NORTH OF THE STONE (GLO = 7.26') FOR THE NW COR. SEC. 18 COHOCTAH TWP. PIOTROWSKI'S IRON IS LOCATED S44E 8.17 FEET FROM THE STONE AND ON THE APPROXIMATE CENTERLINE OF GANNON ROAD TO THE EAST. THE OCCUPIED FENCE LINE TO THE WEST IS ABOUT 9.4 FEET SOUTH OF THE FLAT STONE. WE MEASURED NORTH 2644.17 FEET AND SOUTH 2617.88 FEET (OLD RECORDS SAID 2639.34') MEASURES FROM PIOTROWSKI'S IRON ARE 2652.75 FEET NORTH AND 2608.88 FEET SOUTH. D HUGHES HAS RECORDED AN ACT 74 ON THE LOCATION OF THE FOUND STONE, BRICK AND CROCKERY. SITE IS GOOD FOR GPS. BASED ON THE MATERIAL D HUGHES FOUND FOR BOTH CORNERS AND THEIR POSITION TO EACH OTHER RELATIVE THE GLO JOG OF 7.26 FEET, I WOULD RECOMMEND USING THE CORNER D HUGHES FOUND FOR THE SE SECTION CORNER.



CHARLES E GARLOCK, PS
CON97M5

SUCCESSOR TO:

MILES W. BULLOCK, L.S. (1844 TO 1926) ● GRANT H DUNNING, P.E. (1865 TO 1928)
CLAY W. GORDON, RLS (1883 TO 1970) ● LYLE W. MUNSELL, RLS (1904 TO 1987)

4/27

1/15

4