

SURVEY & REMONUMENTATION

FEB 26 2001

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T 4 N R 3 E</u>	<u>J-05</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

9 2000 SEP 28 10 18
 NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI.
 48843

LSC #1286m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3						7							
4		7		8		9		10		11		12	
5										13			
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, JACK K. SMITH, in a field survey on JULY 20, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO, SURVEY DATED: APRIL 15, 1825 BY S. SIBLEY
 GLO WITNESSES: IRONWOOD 5" N43°E 11.22'
 SYCAMORE 11" S63°W 11.88'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FOUND "T" IRON ON TOP OF FOUND ROCK SET BY MILES W BULLOCK IN 1873, AS PER BULLOCK NOTES.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-05: NORTH 1/4 CORNER OF SECTION 14, T4N-R3E, CONWAY TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN.
 SET A 1 1/4" X 36" BREAKAWAY STEEL PIPE WITH LIVINGSTON COUNTY REMON BRASS CAP # 35999.

N30°W	SP & LIV. COUNTY REMON. TAG ON THE WEST SIDE OF A UTILITY POLE	58.49'
N30°E	SP & LIV. COUNTY REMON. TAG ON THE EAST SIDE OF A GUY POLE	53.62'
S45°W	CENTER LINE OF A 2" STEEL STREET SIGN POST	45.76'
S85°E	CENTER LINE OF THE NORTHERLY LEG OF "ARROW" SIGN	19.41'

Signed by



Date JULY 20, 2000

Surveyor's Michigan License No. 35999



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JANUARY 1983
 REVISED MAY 14, 1975

REVISED JAN, 1983
 REVISED OCT, 1998

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
 PEER GROUP ON 2-16-2000 CO. REP JED