

LIVINGSTON

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Table with 3 columns: FOR CORNERS OF--, LOCATED IN--, CORNER CODE NUMBER. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Section, Lot No., and Private Claims.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law.

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- M-7 Set 4" x 36" concrete monument with aluminum cap on line between N.W. corner, Section 19, T4N, R5E, and S.E. corner, Section 24, T4N, R4E, at the G.L.O. dist. from the N.W. corner, Section 19.
L-8 Set 4" x 36" concrete monument with aluminum cap at the intersection of the N-S and E-W one-quarter lines.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-7 4" x 36" concrete monument with aluminum cap. N 15° W, 12.55', 16" R. Oak, Spike and Tag; N 77° E, 15.53', 7" Maple, Spike and Tag; S 02° W, 21.82', 20" W. Oak, Spike and Tag; S 60° W, 16.70', Twin 6" Maples, Spike and Tag; North 22.44', Concrete Monument; South, 65', North edge of Hidden Lake.
L-8 4" x 36" concrete monument with aluminum cap. North, 10.10', 8" Walnut, Spike & Tag; S 71° E, 9.63', 10" R. Oak, Spike & Tag; N 65° W, 17.92', 4" W. Oak, Spike & Tag; S 25° W, 68.10', Power Pole, Spike & Tag; North, 12.20', 1/2" Iron Rod; S 63° W, 9.36', 10" R. Oak, Spike & Tag; All trees blazed.

SIGNED BY: [Signature] DATE: 12-19-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY: \_\_\_\_\_ DATE: \_\_\_\_\_

APPROVED AND SIGNED BY: \_\_\_\_\_ DATE: \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_