

FILED

JUL 14 9 45 AM '95

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

For corners in
Livingston
(County)

Located In: Corner Code #

- 1. Public Land Survey T 4N R 4E C-12
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Section S _____ T _____ R _____

L. S. C. #410m

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Edward E. Anderson, in a field survey on June 30, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Notes dated: June 20, 1823
GLO Witnesses W. Oak 15" N81°W 7 Lks
W. Oak 14" N40°E 35 Lks

Additional historical data on back

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 1/2" rerod. Fit witnesses by Boss, Benton and Hughes

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-12 W 1/4 COR SEC 32, T4N-R4E

Set 36" x 1 1/4" breakaway iron pipe with brass cap (Liv. Co. Mon. Cor.)
in centerline Fleming Road
N56°E 147.65' S.W. corner house
S63°E 29.20' Spike S/S Triple Wild Cherry
N62°W 24.49' Spike N/S 12" Cedar
N25°W 54.78' Spike E/S 24" Cherry

Signed by E. Anderson
Surveyor's Michigan License No. 11495



Date July 5, 1995

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
REFR GROUP ON 4-5-95



EDWARD E. ANDERSON, P.S., P.E.
RICHARD F. FRANK, P.S.
BRIAN R. SHALTZ, C.S.T.

Members of:
Michigan Society of Professional Surveyors
American Congress on Surveying and Mapping
American Society of Civil Engineers

401 S. Leroy St.
Fenton, Michigan 48430-2164

(313) 629-8974
FAX (313) 629-9069

SUMMARY

March 21, 1995

C-12 WEST 1/4 CORNER OF SECTION 32, T4N-R4E, COHOCTAH TOWNSHIP,
LIVINGSTON COUNTY, MICHIGAN.

Found 1/2" rerod in centerline of Fleming Road (gravel)

Checked and measured to witnesses we found. Found three out of four of Boss witnesses and they checked, Pages 12 and 13 this dossier. Found all of Benton witnesses and they checked, Pages 8 and 9 this dossier. Found 3 of 4 of Hughes witnesses and they checked. We did not find the T iron 3.52' west of the corner, Pages 15 and 16, this dossier.

Distance from the W 1/4 corner to the N.W. corner of said Section 32 is 2654.69' on Benton Survey, pages 8 and 9 this dossier.

Distance from the W 1/4 corner to the S.W. corner of said Section 32 is 2654.55' of Hughes survey, pages 13 and 16 this dossier.

Made a clean sweep of the immediate area and found no additional corners or irons.

Gravel roads running north and south. Roads are flat in both directions.

Terrain is wooded north, south, east, and west. House to the N.E; tree and fence line running to the east and west.

Area is fairly good for G.P.S.

Came to the conclusion that the 1/2" rerod we found is the correct W 1/4 corner of said Section 32.

Edward E. Anderson
P.S.#11495

