

FILED

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Livingston (County)

Located In:

Corner Code #

JUL 14 9 45 AM '95

NANCY HAVILAND REGISTER OF DEEDS LIVINGSTON COUNTY, MI 48843

- 1. Public Land Survey T 4N R 4E C-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

L.S.C.#409m

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Contains numbers 1-36.

I, Edward E. Anderson, in a field survey on June 30, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Notes dated June 20, 1823
G.L.O. Witnesses W. Oak 12" N44°E 53 Lks
W. Oak 12" N60 1/2°W 47 Lks

Additional historical data on back

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found "T" iron. Fit witnesses by Boss, Hughes, and Shellenbarger

COMMUNITY DEVELOPMENT

JUL 14 1995


COMMUNITY DEVELOPMENT

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 SW Cor SEC 32 T4N-R4E

Set 36" x 1 1/4" Breakaway iron pipe with Brass cap (Liv. Co. Mon. Cor.) in centerline Fleming and Allen Roads
N55°E 93.76' S.W. corner house
S67°E 49.55' Spike N/S 36" Cottonwood
S21°W 87.96' Spike E/S Power Pole
S87°W 112.41' Spike N/S 12" Twin Locust

Signed by [Signature] Surveyor's Michigan License No. 11495



Date July 5, 1995

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983

PA. 843 1980, APPROVED BY LIVINGSTON COUNTY REGISTER OF DEEDS JUL 14 1995



EDWARD E. ANDERSON, P.S., P.E.  
RICHARD F. FRANK, P.S.  
BRIAN R. SHALTZ, C.S.T.

Members of:  
Michigan Society of Professional Surveyors  
American Congress on Surveying and Mapping  
American Society of Civil Engineers

401 S. Leroy St.  
Fenton, Michigan 48430-2164

(313) 629-8974  
FAX (313) 629-9069

### SUMMARY

March 23, 1995

C-13 S.W. CORNER SECTION 32, T4N-R4E, COHOCTAH TOWNSHIP,  
LIVINGSTON COUNTY, MICHIGAN

Found "T" Iron on the centerline intersection of Fleming Road to the north  
and Allen Road to the east and west (all roads gravel)

Checked and measured to witnesses we found. Found all of Boss witnesses and  
they checked, pages 11 and 12 this dossier. Found all of Hughes witnesses  
and they checked, pages 15, 17, and 22 this dossier. Found all of Shellenbarger  
witnesses and they checked, pages 18 and 20 this dossier. Found N.W. corner  
of Section 5, T3N-R4E, it checked the distance on Boss and Hughes witness  
sheets, pages 12, 14, 15, and 17 this dossier.

Distance from the S.W. corner to the S.  $\frac{1}{4}$  corner of said Section 32 is  
2646.33' on Boss and Hughes surveys, pages 13, 15, 16, and 17 this dossier;  
and 2646.42' on Boss survey, page 10 this dossier.

Distance from the S.W. corner to the West 1/4 corner of said Section 32 is  
2654.55' on Hughes survey, page 15 and 16 this dossier.

Made clean sweep of immediate area and found no other corners or irons.

Gravel roads running east and west and north. Roads flat to east and west  
and north.

Terrain is open north and south. House to the N.E. and to the N.W.

Good location for G.P.S.

Came to the conclusion that the "T" Iron we found is the correct S.W.  
corner of said Section 32.

Edward E. Anderson  
P.S.#11495

