

MAR 17 2000

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 SEP 10 A 9:04

HANCOCK HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

For corners in

Livingston Located In: Corner Code #
(County)

1. Public Land Survey T 4N R 4E E-10
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LSC #1054m
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John H. Rauser, P.S., in a field survey on 6/12 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-10 Common 1/4 Corner, Sections 28 & 29, T4N-R4E

1823 Wood post placed by Sylvester Sibley, D.S.
N75 1/2 E 12 lks (7.92') 22" W. Oak
S81 1/2 W 25 lks (16.5') 16" W. Oak

(Additional information on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-10 Common 1/4 Corner, Sections 28 & 29, T4N-R4E

Found 3/4" pipe approximately 6' South of gravel centerline.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10 Common 1/4 Corner, Sections 28 & 29, T4N-R4E

Standard Livingston County Remon breakaway monument with brass cap
N45W 31.20' Boss tag in NE fc 5" Oak
N25E 34.88' Hughes tag W. fc 28" Oak
N70E 55.47' Hughes tag SE fc 24" Oak
S5E 31.18' Fnd spike w/cap in SW fc 10" Oak
S20E 21.05' Road sign W fc
North 33.16' Fnd rod w/cap #21270 leaning North
N5W 4.32' Fnd 1" square iron bar 2'+ below grade



Signed by John H. Rauser
Surveyor's Michigan License No. 39096

Date 9/01/99