

FILED

LAND CORNER RECORDATION CERTIFICATE

JUL 14 9 46 AM '95

Filing Requirement of Act 74, Mich. P.A. 1970

HANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

For corners in
Livingston
(County)

Located In: Corner Code #

- 1. Public Land Survey T 4N R 4E E-11
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Section S _____ T _____ R _____

L.S.C.#412m

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Edward Anderson, in a field survey on June 26, 19 95,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current
manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and
5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found
as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Notes dated: June 20, 1823
G.L.O. Witnesses Poplar 18" N 11 1/2°W 6 Lks
Spruce 14" S63 1/2° W 27 Lks

Additional historical data on back


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rerod. Fit witnesses by Boss, Garlock, Benton, Hughes, and Shellenbarger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11 NE COR. SEC. 32, T4N-R4E
Set 36" x 1 1/4" Breakaway iron pipe with brass cap (Liv. Co. Mon. Cor.)
at intersection of Burkhart, Geer, and Chase Lake Roads
N69°E 93.17' Spike S/S 8" Locust
S48°E 79.88' Spike N/S 16" Elm
S54°W 98.08' Spike SE/S 8" Elm
S82°W 132.21' Spike E/S 30" Oak

Signed by E. Anderson
Surveyor's Michigan License No. 11495



Date July 5, 1995

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

PA. 345 1990, APPROVED BY LIVINGSTON COUNTY
DEED GROUP ON 4-5-95



EDWARD E. ANDERSON, P.S., P.E.
RICHARD F. FRANK, P.S.
BRIAN R. SHALTZ, C.S.T.

Members of:
Michigan Society of Professional Surveyors
American Congress on Surveying and Mapping
American Society of Civil Engineers

401 S. Leroy St.
Fenton, Michigan 48430-2164

(313) 629-8974
FAX (313) 629-9069

SUMMARY

March 21, 1995

E-11 N.E. CORNER SECTION 32, T4N-R4E, COHOCTAH TOWNSHIP,
LIVINGSTON COUNTY, MICHIGAN.

Found 1/2" reord 4" below the surface at the intersection of Burkhart, Geer, and Chance Lake Roads (gravel), 3' east of the centerline of Burkhart and Chance Lake Roads and on the centerline of Geer and Chance Lake Roads.

Checked and measured to the witnesses we found. All the witnesses by Boss, Benton, and Garlock, Pages 8, 9, 10, 11, 13, 15, and 20 are gone. Found 3 of 5 of Hughes witnesses and they checked, Page 23 this dossier. Found 2 of 3 of Shellenbarger's witnesses and they checked, Pages 24 and 26 this dossier.

Distance from the NE corner to the North 1/4 of said Section 32 is 2626.98' on Boss Survey, Page 11 this dossier and 2627.56' of Boss surveys, pages 16, 17, 18, and 21 this dossier.

Distance from the N.E. corner to the East 1/4 corner of said Section 32 is 2673.25' on Shellenbarger survey, Pages 24 and 25 this dossier.

Made a clean sweep of immediate area and found no other corners or irons.

Gravel roads running north, south, east and west. Road rising to the north, flat to the south; falls to the east and rises to the west.

Terrain is wooded to the northwest; open to the south and the northeast. House to the N.W.

Good location for G.P.S.

Came to the conclusion that the 1/2" rerod we found is the correct N.E. corner of said Section 32.

Edward E. Anderson
P.S.#11495

