

MAR 17 2000

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

1999 SEP 10 A 9:05

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

corners in

9-

Livingston Located In: Corner Code #

(County)

Public Land Survey		T 4N	R 4E	F-9
		T	R	
Property Controlling	S	T	R	
in Section	S	T	R	
Miscellaneous	S	T	R	
Property in Sec.	S	T	R	

LSC# 1055m
Register of Deeds Stamp & File Number

Lot No. Recorded Plat

Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

John H. Rauser, P.S. in a field survey on June 1999 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

-9 Common 1/4 Corner, Sections 21 & 28, T4N-R4E

1823 Wood post placed by Sylvester Sibley, D.S.
S11E 2.35ch (155.1') 28" W. Oak
West 2.33ch (153.78') 8" W. Oak

(Additional information on back)

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

-9 Common 1/4 Corner, Sections 21 & 28, T4N-R4E

Found a 1/2" re-rod with cap #17022 in swamp grass 70'+ East of the toe of slope.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

-9 Common 1/4 Corner, Sections 21 & 28, T4N-R4E

Standard Livingston County Remon iron pipe with brass cap
N5W 27.52' Fnd Boss tag W. fc in stump
S45W 69.58' Fnd Boss tag in NW fc 15" Cherry
N85E 28.40' Fnd Boss tag N. fc 10" Ash
N80W 80.79' Fnd Boss tag N fc 8" tree



Signed by John H. Rauser
Surveyor's Michigan License No. 39096

Date 9/10/99

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

P.A. 345 1980, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 5-19-99, CO. REP JED