

REF  
MAR 1 2000  
SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

1999 SEP 10 A 9:05

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

For corners in

Livingston Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T 4N R 4E G 9  
T \_\_\_\_\_ R \_\_\_\_\_ G \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

LSC# 1056m  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John H. Rauser, P.S., in a field survey on June 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-9 Common Corner, Sections 21, 22, 27, & 28, T4N-R4E

1823 Wood post placed by Sylvester Sibley, D.S.  
S31½E 45lks (29.70') 15" Spruce  
S61E 43lks (28.38') 8" Spruce

(Additional information on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9 Common Corner, Sections 21, 22, 27, & 28, T4N-R4E

Found ½" iron rod in the approximate center line of the gravel road in line with a old fence line to the east, no occupation to the West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9 Common Corner, Sections 21, 22, 27, & 28, T4N-R4E

Standard Livingston County Remon breakaway monument 0.5'+ below the existing gravel road grade  
S20W 83.26' Hughes tag ESE fc PP  
S80E 25.08' Hughes tag SSW fc 6" Ash  
N40W 30.2' Set spike with LCRemon witness tag in ESE fc 12" Poplar  
N5E 146.05' Set spike with LCRemon witness tag in W fc 20" Walnut

Signed by John H. Rauser  
Surveyor's Michigan License No. 39096

Date \_\_\_\_\_



FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1993

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY

6-2-99 CO. REP JED