

MAR 17 2000

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

1999 SEP 10 A 9:05

For corners in

Livingston Located In: Corner Code #
(County)

1. Public Land Survey T 4N R 4E G-10
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, John H. Rauser, P.S., in a field survey on August 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-10 Common 1/4 Corner, Sections 27 & 28, T4N-R4E
1823 Wood post placed by Sylvester Sibley, D.S.
S88 1/2 E 4.1ch (270.6') 16" B. Oak
N3W 1.26ch (83.16') 14" B. Oak

(Additional information on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-10 Common 1/4 Corner, Sections 27 & 28, T4N-R4E
Found nothing at corner position

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10 Common 1/4 Corner, Sections 27 & 28, T4N-R4E
Standard Livingston County Remon monument with brass cap
S27E 45.43' Set spike with Livingston County Remon tag W. face of 34" Ash
S53W 13.80' Set spike with Livingston County Remon tag in SE face of 12" Ash
N71W 33.46' Set spike with Livingston County Remon tag in S. face of 10" Ash
North 0.53' Set Carsonite Marker Post

Signed by John H. Rauser
Surveyor's Michigan License No. 39096

Date 8/17/99

