

RECORDED

MAR 17 2000

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE

1999 SEP 10 A 9:05

Filing Requirement of Act 74, Mich. P.A. 1970

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

For corners in

Livingston Located in: Corner Code #
(County)

- 1. Public Land Survey T 4N R 4E I-10
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John H. Rauser, P.S., in a field survey on June 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-10 Common 1/4 Corner, Sections 26 & 27, T4N-R4E

1823 Wood post placed by Sylvester Sibley, D.S.
S53E 17lks (11.22') 26" W. Elm
N17W 19lks (12.54') 8" Hickory

(Additional information on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10 Common 1/4 Corner, Sections 26 & 27, T4N-R4E

Found a 1/2" re-rod 1.5'± South of the physical center line of Chase Lake Road, in line with an old fence to the South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10 Common 1/4 Corner, Sections 26 & 27, T4N-R4E

Standard Livingston County Remon break away monument in a monument box
S30W 33.37' Boss N&T E-side twin Oak
North 36.38' Hughes N&T W-side 46" Walnut
S65W 56.06' N&T NW-side 18" Ash
South 33.18' PLB iron

Signed by John H. Rauser
Surveyor's Michigan License No. 39096

Date _____



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
DEER GROUP ON 5-19-99, CO. REP JEO