

REMONUMENTATION CORNER UNDER ACT 345, MICHIGAN PUBLIC ACTS OF 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
LIVINGSTON
(County)

Located In: Corner Code #

1. Public Land Survey	T	4N	R	4E	I-11
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

NOV 10 8 15 AM '94
 NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI
 48843

FILED

L.S.C.#288m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Donald G. Richards September 27th 94

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

"North between Sections 34 & 35 80.00 (chains) to a Lynn 24 inches diameter, corner to Sections 26, 27, 34, & 35" (no further witnesses other than tree for corner post) Sylvester Sibley, June 11th, 1823

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod in north side Basswood tree (see reverse side for research and investigation summary)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Reset with 1 1/4" x 36" iron pipe w/brass cap stamped "Livingston County Monumentation Corner" and "24614"

- S 85 W 32.86' nail/tag* in north side 16" white oak
- S 30 W 24.78' nail/tag* in northwest side 9" white oak
- EAST 67.98' nail/tag* in north root 12" basswood
- N 30 E 35.05' nail/tag* in southeast side 28" cottonwood

*tags read "Livingston County Survey Witness" and are stamped "24614"

Donald G. Richards

(approved by peer group 10-05-94)

Signed by DONALD G. RICHARDS Date October 19, 1994

COHOCTAH I-11

Deputy Surveyor Sylvester Sibley set a wood post to first mark this section corner on April 11th, 1823. There were no County Surveyors records found pertaining to this point.

The first contemporary surveys utilizing this point were performed by Charles E. Garlock in 1988. His survey number 160-56 in Section 27 identifies this corner as a "Found 1/2" Iron rod in north side 10" basswood", and he provides five witnesses for the point. One month later, Garlock recorded this information as LSC 1390.

On September 27th, 1994, the fieldcrew recovered this point as described by Garlock some six years ago. With minor variations in measurement, all five of his witnesses were recovered also.

The distance from this section corner to quarter corner H-11 compared favorably with the same lengths as noted on surveys by Garlock in 1974 and 1988. No recorded measurement to quarter corners J-11 of I-12 were located on the public record.

Donald G. Richards, PS 24614
October 3, 1994
Approved October 5, 1994