

**SURVEY & REMONUMENTATION**

FEB 25 1999

SECTION

**1998 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**FILED**

1998 OCT 14 P 2:11

For corners in

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

Livingston Located in: Corner Code #  
(County)

9

LSC 909M

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 4N R 4E K-9  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, John H. Rauser, P.S., in a field survey on September 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

**K-9 Common Section Corner, Sections 24, 25, 26, & 27, T4N-R4E, Cohoctah Township, Livingston County**

1823 Wood post placed by John Mullett, D.S.: Poplar 16" N25W 2.01 lks  
W. Oak 15" N68W 2.87 lks

(Additional information on back)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

**K-9 Common Section Corner, Sections 24, 25, 26, & 27, T4N-R4E, Cohoctah Township, Livingston County**

Found no evidence of original government corner. Found a concrete monument with a brass cap stamped "#18655 D.L.B. MDNR" as per 1981 survey and act 74 by Donald L. Bissell.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**K-9 Common Section Corner, Sections 24, 25, 26, & 27, T4N-R4E, Cohoctah Township, Livingston County**

Left concrete monument with brass cap, stamped "18655 D.L.B. MDNR", in place as recovered

- S75E 146.11' Fnd rod/cap #12024
- N86W 33.66' Fnd rod/cap #19826
- N06W 115.09' Set Livingston County witness on E fc of R/R tie iron post, leaning NW, but sturdy
- N80W 166.66' Set Livingston County witness on N fc of 14" Elm
- N71W 141.56' Set Livingston County witness on N fc of 12" Elm

Signed by John H. Rauser  
Surveyor's Michigan License No. 39096

Date \_\_\_\_\_

