

SURVEY & REMONUMENTATION

FEB 24 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

LIVINGSTON
(County)

Located in:

Corner Code #

1. Public Land Survey

T 4N R 5E G-13

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

1997 SEP 23 A 10:18

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C.#704m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Jack K. Smith, in a field survey on July 20, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-13 The Southwest Corner of Section 34, Deerfield Township was set by John Mullett for the GLO in 1823.

The original witnesses are:

W Oak 24" N44°W 46 lk (30.4')
W Oak 18" N84°E 78 lk (51.5')

NOTE: NONE OF THE ORIGINAL WITNESSES COULD BE FOUND OR PERPETUATED. SEE THE BACK OF THIS SHEET FOR ADDITIONAL HISTORICAL DATA.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13 Found 1" buggy axle set by McCreary in 1907.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 Southwest Corner, Section 34, T4N, R5E - Set 1 1/4" x 30" steel pipe with 6" break-off section and brass cap marked as "Livingston County Remonumentation Corner".

S16°E Set nail/tag in West side 35" Oak 26.16'
S56°E Set nail/tag in West side 34" Maple 51.62'
N70°E Set nail/tag in South side 29" Walnut 89.55'
N04°E Set nail/tag in West side 32" Walnut 94.80'

Signed by [Signature]
Surveyor's Michigan License No. 35999

Date July 20, 1997

July 12, 1997

G-13 T4N - R5E: SOUTHEAST CORNER, SECTION 33, DEERFIELD TOWNSHIP

MONUMENTATION

G-13 was originally set by John Mullett for the GLO in 1823. This corner is presently marked by a 1" buggy axle set by McCreary in 1907.

MEASUREMENTS

Current measure is 2595.70 feet to the east and 2639.11 feet to the west. Post 1970 measures to east and west compare well. The closing corner falls 238.49 feet east of G-13 (GLO computes to 231.0 feet).
13

OCCUPATION


The corner falls 5 feet south of the centerline of Allen Road (gravel) and 6 feet east of the centerline of Mack Road (gravel to the north only). A sweep of the area around the corner with a magnetic locator did not reveal any alternate corner positions. This corner is heavily masked for GPS and will probably not make a good GPS corner.

RECORDATION

There are 2 Act 74s filed on this corner and it has been used for 14 Act 132s.

SUMMARY

The current location of the corner has been used since 1907 and is directly retraceable through witness history. It has been used for all known previous surveys in the area and by nearly every local surveying firm. I therefor recommend that the existing 1" buggy axle be replaced with a Livingston County Remonumentation pipe and cap.


Jack K. Smith, PS
Desine Inc.

