

**SURVEY & REMONUMENTATION**

FEB 25 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**FILED**

For corners in

<u>LIVINGSTON</u> (County)	Located in:	Corner Code #
1. Public land survey	<u>T4N R5E</u>	<u>H-11</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	& <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	& <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	& <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	& <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

1998 OCT 20 P 1:22

NANCY HAVILAND  
 REGISTER OF DEEDS  
 LIVINGSTON COUNTY, MI.  
 48843

LSC939M

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, MARY A. BARNWELL, in a field survey on SEPTEMBER 17, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1823 SIBLEY SET POST  
 HICKORY 12 S16E 79 (52.1')  
 YELLOW OAK 14 N27E 1.71 (112.9')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 1/2" REROD 1.8 FEET SOUTH OF THE CENTER LINE OF FAUSSETT ROAD (PAVED). THIS CORNER POSITION AGREES WELL WITH WITNESSES OF RECORD SINCE 1963.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11 SOUTH 1/4 CORNER SECTION 27 / NORTH 1/4 CORNER SECTION 34, T4N, R5E, DEERFIELD TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN;  
 RESET FOUND 1/2" IRON WITH 1 1/4" X 36" BREAKAWAY STEEL PIPE WITH LIVINGSTON COUNTY REMONUMENTATION BRASS CAP WITH SURVEYOR #35999 @ 1/2 FOOT BELOW THE SURFACE OF FAUSSETT ROAD IN MONUMENT BOX.

S43°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN NE SIDE 40" OAK 35.87'  
 S77°W NAIL WITH LIVINGSTON COUNTY REMON TAG IN NORTH SIDE 24" CHERRY 90.42'  
 S08°W NAIL WITH LIVINGSTON COUNTY REMON TAG IN EAST SIDE FENCE POST 24.55'  
 N05°W NAIL WITH LIVINGSTON COUNTY REMON TAG IN WEST SIDE 18" CHERRY 60.73'

Signed by Mary A. Barnwell

Date 10/1/98

Surveyor's Michigan License No. 33971



PA. 345 1990, APPROVED BY LIVINGSTON COUNTY  
 PEER GROUP ON 9-2-98 CO. REP JED

BOOK APPROVED BY MICHIGAN BOARD OF PROFESSIONAL SURVEYORS  
 RECORDED BY REC'D  
 INDEXED BY IND  
 DEPOSITED OCT. 1998