

SURVEY & REMONUMENTATION

FEB 24 1998

FILED 9-

SECTION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>5E</u>	<u>H-13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

1997 SEP 23 A 10:18

NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI.
 48043

L.S.C.#705m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jack K. Smith, in a field survey on July 20, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13 The South 1/4 Corner of Section 34, Deerfield Township was set by John Mullett for the GLO in 1823.
 The original witnesses are:
 Tamarack 20" N35°E 95 lk (62.7')
 Tamarack 8" N83°W 77 lk (50.8')

NOTE: NONE OF THE ORIGINAL WITNESSES COULD BE FOUND OR PERPETUATED. SEE THE BACK OF THIS SHEET FOR ADDITIONAL HISTORICAL DATA.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 Found 1/2" re-rod on the centerline of Allen Road (gravel)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 South 1/4 Corner, Section 34, T4N, R5E - Set 1 1/4" x 30" steel pipe with 6" break-off section and brass cap marked as "Livingston County Remonumentation Corner".
 N51°W Set nail/tag in SW side 22" Ash 58.81
 N28°W Set nail/tag in SW side 18" Ash 35.19'
 S14°E Set nail/tag in East side 24" Ash 35.17'
 N54°W Set witness pipe* and carsonite post 23.14'

* 36"X1" iron pipe with brass cap marked "Livingston County Remonumentation Witness"

Signed by Jack K. Smith Date July 20, 1997
 Surveyor's Michigan License No. 35999

July 12, 1997

H-13 T4N - R5E: SOUTH 1/4 CORNER, SECTION 34, DEERFIELD TOWNSHIP

MONUMENTATION

H-13 was set by John Mullett for the GLO in 1823. This corner is currently marked by a 1/2" re-rod which was shown as found by Boss Engineering in 1972.

MEASUREMENTS

Current measure is 2648.68 feet to the east and 2595.70 feet to the west. Post 1970 measures to east and west compare well. The closing corner falls 291.89 feet east of H-13 (GLO computes to 247.5 feet).

OCCUPATION


H-13 falls on the centerline of Allen Road (gravel). There is light occupation in the northwest quadrant relative to this corner. A sweep of the area around the corner with a magnetic locator did not reveal any alternate corner positions. This corner is open for GPS.

RECORDATION

There is an Act 74 filed by Oscar Boss in 1973 which shows a found 1/2" iron at H-13. The witnesses from 1973 still check. The corner has been shown on 10 Act 132s.

SUMMARY

The current location of the corner has been used for numerous surveys in the area and no other position has been used that I could find. Considering the 20 plus years of continuous use I recommend that the existing 1/2" iron be replaced with a Livingston County Remonumentation pipe and cap.


Jack K. Smith, PS
Desine Inc.

