

FEB 25 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

LIVINGSTON  
(County)

Located In:

Corner Code #

- 1. Public land survey T4N R5E 112
- 2. Property Controlling in Section § T R
- 3. Miscellaneous Property in Sec. § T R

1998 OCT 20 P 1:22

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

LSC941M

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

MARY A. BARNWELL in a field survey on SEPTEMBER 17, 1998 do hereby state that under requirements of D.A. 74 Michigan D.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management, or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1823 SIBLEY SET POST  
WHITE OAK 18 N71E 43 (28.4')  
WHITE OAK 14 S55W 41 (27.1')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 1/2" REROD 8 FEET WEST OF THE CENTERLINE OF ARGENTINE ROAD (PAVED). THIS CORNER POSITION AGREES WELL WITH WITNESSES OF RECORD SINCE 1962.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12 EAST 1/4 CORNER SECTION 34 / WEST 1/4 CORNER SECTION 35, T4N, R5E, DEERFIELD TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN:  
RESET FOUND 1/2" REROD WITH 1 1/4" X 36" BREAKAWAY STEEL PIPE WITH LIVINGSTON COUNTY REMONUMENTATION BRASS CAP WITH SURVEYOR #35999 @ 1/2 FOOT BELOW THE SURFACE OF THE ROAD IN MONUMENT BOX.  
(CORNER IS 0.05' SOUTH OF CENTER OF LID OF MONUMENT BOX)

- EAST NAIL WITH LIVINGSTON COUNTY REMON TAG IN NORTH SIDE UTIL. POLE 63.45'
- S88°W NAIL WITH LIVINGSTON COUNTY REMON TAG IN NORTH SIDE 24" CHERRY 28.51'
- N75°W NAIL WITH LIVINGSTON COUNTY REMON TAG IN NORTH SIDE TRIPLE HICKORY 42.21'
- N30°W NAIL WITH LIVINGSTON COUNTY REMON TAG IN EAST SIDE 12" DBL. OAK 50.04'

Signed by [Signature]

Date 10/1/98

Surveyor's Michigan License No. 33971



PA. 345 1990, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 9-2-98 CO. REP JED

FILED ACCORDING TO MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, PA 345 1990  
RECORDED BY MDE  
OCTOBER 20, 1998  
RECORDED BY MDE