

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 4N R 5E	J-07
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

9r

1999 NOV 22 A 10:08

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

LSC# 1096m

Register of Deeds Stamp & File  
Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, MARY A. BARNWELL, in a field survey on SEPTEMBER 29, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-07 Deerfield Township was set be the GLO in 1823. The original Witnesses are:  
Yellow Oak 14" S. 81° W. 43 Links (28.4')  
Yellow Oak 24" N. 72° E. 42 Links (27.7')

NOTE: None of the original witnesses could be found or perpetuated. See the back of this sheet for additional historical data.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-07 Found 1/2" Iron Rod at the centerline of Center Road (gravel surface running East-West) - old fence running North - no occupation to the South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-07 North 1/4 Corner, Section 23, T4N, R5E - Replaced the 1/2" Iron Rod with 36"x 1 1/4" Steel Breakaway Pipe with Brass Cap marked as "Livingston County Monumentation Corner"

N 60° W Set Nail/Remon Washer S/S 12" Oak 51.16'  
N 16° E Set Nail/Remon Washer W/S 20" Cottonwood 17.88'  
N 47° E Set Nail/Remon Washer SE/S 16" Oak 81.43'  
S 10° E Set 36" x 1 1/4" Pipe W/Remon Witness Brass Cap 25.61' and a Carsonite Post behind it

Signed by Mary A. Barnwell Date 11-4-99

Surveyor's Michigan License No. 33971

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

